BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of the work:- Desilting of SWD from Manyatha Paras Appartment (Near Chamundeshwari temple) to Defence layout in ward no. 06 Thanisandra.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
1	29015.95	KSRRB M300-14. Excavation for roadwork in all type of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications.	cum	146.96	Rupees One Hundred Forty Six and Ninety Six Paise Only
2	2400.00	KSRRB 200-8 Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle , Removal of stumps, disposal of unserviceable materials,stacking of serviceable materials labour charges complete as per specifications.	Sqm	6.48	Rupees Six and Forty Eight Paise Only
3	150.00	Hiring of pump for Dewatering using 3.5Kl/hr capacity pump	hr	54.00	Rupees Fifty Four Only
4	152.00	Hiring of Hydraullic excavator 1cum Bucket	hr	1130.00	Rupees One Thousand One Hundred Thirty Only
5	60.00	Hiring of Tipper Lorry operator and fuel	day	1920.00	Rupees One Thousand Nine Hundred Twenty Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

24/11

24/11